GOVERNMENT INDUSTRIAL AND TESTING LABORATORY, MALLESWARAM P. O., BANGALORE.

Abstract Notification dated 8th December 1938.

The attention of the public is invited to the notification calling for tenders for the purchase of Old Cornish Boiler, during the year, 1938-39, published on page 2178, Part VI of the *Mysore Gazette*, dated 1st December 1938.

The last date for receiving tenders is 20th December 1938.

K. PARTHASARATHI,
Assistant Director.

GOVERNMENT OF MYSORE, ELECTRICAL DEPARTMENT.

OFFICE OF THE SUPERINTENDENT, POWER AND LIGHTING, BANGALORE.

PROVIDING ELECTRIC LIGHTS TO THE NEWLY BUILT POLICE LINES NEAR "A" STATION, HIGH GROUNDS, BANGALORE.

Abstract Notice.

Attention is drawn to this office notice, inviting tenders for the above work, published in Part VI, Page 2195 of the *Mysore Gazette*, dated 18th December 1938. The last date for receiving tenders is 16th December 1938, and the earnest money required is Rs. 30.

PROVIDING ELECTRIC LIGHTS TO THE EXTENSION OF THE 2ND FLOOR OF STATE LIFE INSURANCE OFFICE AT CUBBON PARK, BANGALORE.

Abstract Notice.

Attention is drawn to this office notice, dated 2nd December 1938, inviting tenders for the above work, published in Part VI, pages 2195 and 2196 of the *Mysore Gazette*, dated 8th December 1938. The last date for receiving tenders is 23rd instant, and the earnest money required is Rs. 30.

C. R. GOWDA,
Superintendent.

OFFICE OF THE SUPERINTENDENT, POWER AND LIGHTING, KOLAR GOLD FIELDS.

Notification dated 28th November 1938.

Notice is hereby given that sealed tenders will be received from Licensed Electrical Contractors at the Office of the Superintendent, Power and Lighting, K. G. F., up to 3 P.M. on 26th December 1938 for Electrification of Railway Station at Chintamani.

The quantities are not guaranteed. The work should be completed before the 20th January 1939.

2. The place and conditions may be ascertained from the Line Inspector, Power and Lighting, Chintamani.

3. The tenders should be accompanied by a statement in the form given below showing the rates at which the different items will be executed. The materials to be used on the work should strictly conform to the specifications and executed as per regulations and instructions of the department.

4. Each tender must be accompanied by a deposit of Rs. 30 in cash as earnest money and be superscribed "Tender for Electrification of Railway Station at Chintamani," in default of which the tenders will be rejected.

5. The final acceptance of the tender will rest with the Superintendent, Power and Lighting, Champion Reef, K. G. F., who does not bind himself to accept the lowest tender or to assign any reason whatever for the rejection of the tender.

6. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute the usual agreement, in default of which his tender will be considered as cancelled and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted will be posted on the Notice Board in the Office of the Superintendent, Power and Lighting, K. G. F., and of the Assistant Superintendent, Rural areas, Kolar, in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders the earnest money on rejected tenders will be refunded.

9. Materials that may be found necessary during execution should be supplied by the contractor himself.

10. In all matters not specifically produced, the decision of the Superintendent, Power and Lighting, Kolar Gold Fields, will be final and legally binding.

11. Approximate quantities of materials required for Electrification of Chintamani Railway Station :—

INTERIOR WIRING.

	Particulars	*Quantity*
1.	Supplying and fixing mains in $\frac{5}{8}$" braized conduit using No. 7-.036 S. W. G., V. I. R., 2,500 meg ohms grade wire tested for 600 volts complete with bends, bushings, etc., from the pole to meter board	40 R.ft.
2.	Supplying and fixing a Teakwood Board 2′×2′×2″ wired with the following :— (1) D. P. S. T. Iron Clad Switch 15 amps. with fuse arrangements No. 1 .. (2) D. P. S. T. Iron Clad switch 30 amps., with fuse arrangements. No. 2 for control of yard lights. Complete with hinged glass door and locking arrangements	1 Set
3.	Supplying, fixing and wiring with No. 12 B. & S. insulated wire 2,500 meg ohms grade tested for 600 volts for mains and No. 14 B. & S. for outlets in 2″×1″ Teakwood casing with two coats of shalac varnish using brass screws for capping and wall plugs, etc.	16 lights and 2 wall plugs.
4.	Supplying, fixing and wiring bakelite 5 amps. controlling switches, G. E. C. ..	10
5.	Supplying, fixing and wiring bakelite 5 amps. controlling switches G. E. C. for combined wall plug and switch	3
6.	Supplying, fixing and wiring :—	
	(*a*) $\frac{5}{8}$" rigid iron pendents 8′ to 10′ long with B. C. holders back plate, etc., complete	3
	(*b*) $\frac{5}{8}$" rigid iron pendents 4′ to 5′ long with B. C. holders back plate, etc., complete	2
	(*c*) $\frac{5}{8}$" Brass Brackets heavy pattern 9″ long with B. C. holders complete (Bangalore Type)	5
	(*d*) $\frac{5}{8}$" batten holders, G. E. C. complete	6
	(*e*) Shades white opal or tin enamelled	16
	(*f*) Lamps, M. F. B. C., 225 volts, 30 to 60 watts pearl, gas-filled, $\frac{1}{2}$ watt, (Mazda or Osram)	16
7.	Masonry, patching and colour washing and painting, etc.	1 item

EXTERIOR WIRING.

1.	Supplying and fixing S. M. Rails 24′ long (Tarred)	8
2.	Supplying and fixing guy sets complete with 7 strand of $\frac{3}{8}$" G. I. wire with ground pipe and Turnbuckles	4 sets
3.	Supplying and fixing 2 Pin Double cross arms with insulators with pins for 600 volts, bolts and nuts, clamps, etc., tarred complete	7
4.	Supplying and fixing 2 Pin single cross arms with Insulators with pins for 600 volts, bolts and nuts, clamps, etc., tarred complete	3
5.	Supplying, fixing and wiring 2 batten holders inside the latrine	2
6.	Supplying and stringing overhead lines of No. 6 B. & S. bare copper wire (2 wire) from the Government pole to the consumer pole to the platform lighting ..	75 lbs.
7.	Supplying, fixing and wiring $\frac{3}{4}$" galvanised iron pipe goose-neck fitting with clamps for S. M. Rails and water-tight, shades to be used for yard lights to be fixed at 16′ above ground level	6 sets
8.	Supplying and fixing lamps, M. F. B. C. 230 volts, 30 to 60 watts, $\frac{1}{2}$ watt, clear, gas filled Mazda or Osram for platform	8
9.	Supplying and fixing up a guarding made in No. 10 B. W. G. galvanised wire for telephone line crossing, including angle iron, clamps, bolts, and nuts, etc.,	1 item
10.	Grounding with tinned copper-plate, etc.	1

N.B.—The lights on the platforms should be controlled by a totally different switch in the Station Master's Room.

R. RAMACHANDRA RAO,
Superintendent.

OFFICE OF THE GENERAL SUPERINTENDENT, SHIMSHA NEW PROJECT, SHIMSHAPURA.

Abstract Notification dated 3rd December 1938.

Subject :—PROVIDING ELECTRIC LIGHTS TO THE BUILDINGS AT SHIMSHAPURA.

Attention is drawn to this office Notification dated 19th November 1938, inviting tenders for the above work, published in Part VI, pages 2142-2149, of the *Mysore Gazette*, dated 1st December 1938. The last date for receiving tenders is 20th December 1938 and the date of opening of tenders is 21st December 1938 (and not the 16th instant as published in the *Gazette* of 1st December 1938). The earnest money required is Rs. 500.

A. C. MUNIRATHNAM MUDALIAR,
General Superintendent.